

INSPECTION SCHEDULE

It is your responsibility to call for inspections. Failure to request inspections may delay completion of your project or cause legal action.

The following inspections must be complied with:

- 1) Footing inspection before pouring, footings will need to be formed with re-rod in place.
- 2) Basement walls (block) are built to a required design with re-rod and grouting and/or pilasters - To be inspected before sill plate is installed.
- 3) Rough inspections are required before any insulation or sheathing is applied but after, plumbing, electrical and mechanical state inspectors have approved their rough inspections.
- 4) Final inspections are required before building is occupied or sold. Fire alarms, handrails, steps or landings must be completed.

A 24 HOUR NOTICE FOR INSPECTIONS IS REQUIRED